



Hopkins County Hospital District

## Request For Proposal

2022 – New Build HQ

Hopkins County Hospital District/Hopkins County EMS

PROPOSALS DUE BY: April 8, 2022 by 12:00 pm



# Hopkins County Hospital District

## Request for Proposal

RFP: AV/Security	Proposal Due By: <b>April 8, 2022</b>	Hopkins County EMS
<b>Project Overview:</b>  New building HQ for HCHD to house administration and EMS services.		
<b>Project Goals:</b> <ul style="list-style-type: none"><li>● Access Control</li><li>● Audio/Visual for Conference Rooms</li><li>● Security Cameras</li></ul>		
<b>Scope of Work:</b>  <b>Audio / Video</b>  <b>Training Room 116</b> <p>The Training Room is a 34'x23' space with classroom style seating that can be configured into front facing rows or into a "U" shaped configuration. The space will allow for training of large groups of people by electronic means, including PC's, and will utilize a projection system for image magnification. Based on these requirements and size of the space, provisions for speech reinforcement must be provided. The ability to video conference from the space which shall be priced as an option. Due to the complexity of the system, a control system must be included as part of this RFP.</p> <p>Provide and install the following components and/or capabilities</p> <ul style="list-style-type: none"><li>- Image Magnification System<ul style="list-style-type: none"><li>○ Projector</li><li>○ Electric Screen</li><li>○ Wireless PC Presentation System</li></ul></li></ul>		



# Hopkins County Hospital District

- HDMI input plate (wall or podium mounted)
  - Annotation System
- Local Sound Reinforcement System
  - Ceiling Microphones
  - Ceiling Speakers
  - Wireless microphone(s)
  - Podium Microphone
  - Associated DSP and Amplification
- Control System
  - Components as required to control source select, volume and other options as required
- Video Conference System (Option)
  - Video Codec
  - OFE Provided Laptop (Teams, Zoom)
  - Conferencing Camera(s)

## **Conference Room 108**

The Conference Room is a small space measuring approximately 11'x12' and would likely seat 4-6 people in the center of the space. The space will allow for meeting of a small group and would utilize an appropriately sized display for image magnification and annotation as well as a video conferencing capability. Due to the size of the space, speech reinforcement will not be required.

Provide and install the following components and/or capabilities

- Image Magnification System
  - Promethean Activpanel or Similar Solution for Display and Annotation
  - Wireless PC Presentation System
  - HDMI input plate (wall mounted)
- Local Sound Reinforcement System
  - Ceiling or Wall Mounted Microphone
  - Ceiling or Wall Mounted Speaker
  - Associated DSP and Amplification
- Video Conference System
  - Video Codec
  - OFE Provided Laptop (Teams, Zoom)
  - Conferencing Camera(s)

## **Dispatch**

- Install (2) OFE wall mounts and displays. Further discussion may take place pending CAD system display output capabilities



# Hopkins County Hospital District

## **Exec Offices (2)**

- Install (1) each OFE wall mounts and displays.

## **Apparatus Bay**

- Paging is required via Telco interface. Components TBD based on provided phone system but we'll provision for a Mixer/Amp and Speaker
- Local DAS is required for this area

## **Security:**

Install 12 Cameras, 7 Internal, an 5 External. Also provide a Cloud Based ACS for 20 doors with 2 doors that have capability of unlocking remotely

Access Control System = ACS

Furnish and Install a Cloud Based ACS system. Brivo, Verkada, PDK

Furnish and Install 2 Maglocks on Lobby doors.

Rex

Push To Exit Button / with Signage

timer for Exit Button

Card Reader.

Furnish and install 18 Door Strikes.

Door Contact

Card Reader

. Furnish and Install all Composite cabling to each door from ACS panel

Closed Circuit Television = CCTV

Furnish and Install NVR with 45 days of retained recording. Digital Watchdog, Verkada

Furnish and Install 12 Turret style Cameras @ 4mp and a 2.3 - 8mm Lens



# Hopkins County Hospital District

Camera Fitted Junction Box  
3ft. Patch Cable  
Surface mount jack  
Furnish and Install Cat 6 cabling from each camera and to the NVR.

Furnish and Install all Patch cables and POE Switches.

Furnish and install wall mounted cabinet for NVR.

## Evaluation Metrics and Criteria

- Qualifications, experience, references, and ability to carry out the described work
- Proposed methodologies and processes to accomplish work
- Fees / Expenses
- Completeness of proposal and adherence to RFP

## Submission Requirements

- #1 – Proposal submissions should be in a binder with cover page and total price
- #2 – Reference Page must be included
- #3 – Timeline from install to completion with estimated dates

Project Due By: **April 8, 2022 by 12:00pm**

Budget: **n/a**

Contact: **Brent Smith**

Email:  
[brent.smith@hchdems.com](mailto:brent.smith@hchdems.com)

Phone #: **903-438-4372**